



यशोधरा गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय

बैदौली, कपिलवस्तु
लुम्बिनी प्रदेश, नेपाल

पत्र संख्या :- २०८१/८२

चलानी नम्बर :-

२४९९

मिति : २०८२।१।२३


श्री ए.पि.एच.आइ.टी. सोलुसन्स एण्ड कन्सल्टेन्ट्स, क.ब.न.पा-३, कपिलवस्तु ।

श्री पिउस सप्लायर्स, क.ब.न.पा-७, तौलिहवा ।

श्री गोल कम्प्युटर एण्ड सप्लायर्स, क.ब.न.पा-१, कपिलवस्तु ।

विषय : कोटेशन/दररेट उपलब्ध गराइदिने सम्बन्धमा ।

प्रस्तुत विषयमा आर्थिक वर्ष ०८१।०८२ को स्वीकृत वार्षिक बजेट तथा कार्यक्रम अन्तरगत यशोधरा गाउँपालिका अन्तरगत स्वास्थ्य चौकीहरूमध्ये बसन्तपुर स्वास्थ्य चौकी, बैदौली, आंधारभूत अस्पताल र सिहोखोर स्वास्थ्य चौकीमा सोलर ब्याकप जडान कार्यका लागि बजेट विनियोजन भएकोमा उक्त कार्य गर्न कोटेशन माग गर्ने भनि खरिद समितिबाट निर्णय भएकोले पत्र प्राप्त भएको मितिले ५ दिन भित्र संलग्न BOQ तथा स्पेसिफिकेशन बमोजिम कोटेशन/दररेट उपलब्ध गराइदिनु हुन व्यहोरा अनुरोध छ ।


२०८२।१।२३
(ऋषभ देव खनाल)

प्रमुख प्रशासकीय अधिकृत

प्रमुख प्रशासकीय अधिकृत



Yasodhara Rural Municipality

Office of Rural Municipal Executive

BILL OF QUANTITY

Name of Project:- Solar Backup System Installation

Name of Beneficiary:- Yasodhara Rural Municipality.

Location : Basantpur Health Post, Baidauli Hospital, Shihokhor Health Post

[Signature]
प्रमुख प्रशासकीय अधिकृत

Item	Description	Quantity	Unit	Unit Price		Total Price (in NRs)
				In Figure	In Words	
1	Supply and fitting of Polycrystalline Solar Panel	2400	wp			
2	Supply and fitting of 2 kVA hybrid inverter	3	PCS			
3	Supply and fitting of 150 Ah Lead Acid Battery @10C 12VDC as per attached	6	Nos			
4	Supply and fitting TUV certified twin core solar DC cable of 10 sq. mm.	195	Rm			
5	Supply and fitting 2.5 mm PVC insulated	4	Roll			
6	Supply and fitting Double Pole AC MCB of 16 A; NS Standard.	3	Nos			
7	Supply and fitting Double Pole DC MCB of 16 A; NS Standard.	3	Nos,			
8	Supply and fitting Copper Earthing Wire of 10 sq. mm PVC insulated NS Standard Copper Wire.	185	Rm.			
9	Supply and fitting of Aluminium/GI Module Solar Panel Mounting Structure with Nuts bolts	12	Set			



प्रमुख प्रशासकीय अधिकृत

10	Supply, fitting and installation of Earthing system (Diameter copper clad	3	Set		
11	Transportaion	1	Lumpsum		
12	Installation, Testing and Commissioning of Charge of 2.4 kwp solar backup system with cable tie, nuts, bolts, clamps as as directed by engineer.	1	Set		
Sub-Total Amount					
VAT @ 13% Sub-Total Amount					
Grand Total Amount					

The price shall include all customs duties and sales and other taxes already paid or payable on the components and raw material used in the manufacture or assembly of the item or the customs duties and sales and other taxes paid on the previously imported item offered ex warehouse, ex showroom, or off-the-shelf. These factors should not be entered separately.

Name of Contractor :

Authorized Signature :

Date :